14434.03

HANSEN HALL - LEVEL 300/400 RENOVATIONS

CONSTRUCTION PACKAGE

SECTION 078446 - FIRE-RESISTIVE JOINT SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

- 1. Joints in or between fire-resistance-rated constructions.
- 2. Joints at exterior curtain-wall/floor intersections.
- 3. Joints in smoke barriers.

B. Related Sections:

1. Section 078413 "Penetration Firestopping" for penetrations in fire-resistance-rated walls, horizontal assemblies, and smoke barriers.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Product Schedule: For each fire-resistive joint system. Include location and design designation of qualified testing agency.
 - 1. Where Project conditions require modification to a qualified testing agency's illustration for a particular fire-resistive joint system condition, submit illustration, with modifications marked, approved by fire-resistive joint system manufacturer's fire-protection engineer as an engineering judgment or equivalent fire-resistance-rated assembly.

1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For qualified Installer.
- B. Installer Certificates: From Installer indicating fire-resistive joint systems have been installed in compliance with requirements and manufacturer's written recommendations.
- C. Product Test Reports: Based on evaluation of comprehensive tests performed by a qualified testing agency, for fire-resistive joint systems.

14434.03

HANSEN HALL - LEVEL 300/400 RENOVATIONS

CONSTRUCTION PACKAGE

1.5 QUALITY ASSURANCE

- A. Installer Qualifications: A firm that has been approved by FM Global according to FM Global 4991, "Approval of Firestop Contractors," or been evaluated by UL and found to comply with UL's "Qualified Firestop Contractor Program Requirements."
- B. Fire-Test-Response Characteristics: Fire-resistive joint systems shall comply with the following requirements:
 - 1. Fire-resistive joint system tests are performed by a qualified testing agency acceptable to authorities having jurisdiction.

1.6 PROJECT CONDITIONS

- A. Environmental Limitations: Do not install fire-resistive joint systems when ambient or substrate temperatures are outside limits permitted by fire-resistive joint system manufacturers or when substrates are wet due to rain, frost, condensation, or other causes.
- B. Install and cure fire-resistive joint systems per manufacturer's written instructions using natural means of ventilation or, where this is inadequate, forced-air circulation.

1.7 COORDINATION

- A. Coordinate construction of joints to ensure that fire-resistive joint systems are installed according to specified requirements.
- B. Coordinate sizing of joints to accommodate fire-resistive joint systems.
- C. Individual subcontractors are responsible for sealing all penetrations made by their respective trades, in walls, ceilings, floors, shafts, and other parts of the building construction, whether made in new or existing construction. Sealing is required to maintain fire, smoke or other required ratings or qualities of the penetrated construction. As with all other general construction requirements, the General Contractor is responsible for directing this work of the subcontractors.
- D. The General Contractor and individual subcontractors are responsible for reporting any existing penetrations in walls, ceilings, floors, shafts and other parts of the building construction discovered while uncovering in-place work. Subcontractors are required to report to the General Contractor. The General Contractor is required to report to the Architect for direction.

PART 2 - PRODUCTS

2.1 FIRE-RESISTIVE JOINT SYSTEMS

A. Where required, provide fire-resistive joint systems that are produced and installed to resist spread of fire according to requirements indicated, resist passage of smoke and other gases, and maintain original fire-resistance rating of assemblies in or between which fire-resistive joint

14434.03

HANSEN HALL - LEVEL 300/400 RENOVATIONS

CONSTRUCTION PACKAGE

systems are installed. Fire-resistive joint systems shall accommodate building movements without impairing their ability to resist the passage of fire and hot gases.

- B. Joints in or between Fire-Resistance-Rated Construction (Provide fire-resistive joint systems with ratings determined per ASTM E 1966 or UL 20790) Joints at Exterior Curtain-Wall/Floor Intersections (Provide fire-resistive joint systems with rating determined by ASTM E 119 based on testing at a positive pressure differential of 0.01-inch wg (2.49 Pa) or ASTM E 23070) Joints in Smoke Barriers (Provide fire-resistive joint systems with ratings determined per UL 20790):
 - 1. Fire-Resistance Rating: Equal to or exceeding the fire-resistance rating of construction they will join.
 - 2. Manufacturers: Subject to compliance with requirements, provide products by only one of the following for all the types of joints listed above:
 - a. Grace Construction Products.
 - b. Hilti, Inc.
 - c. Johns Manville.
 - d. 3M Fire Protection Products.
 - e. Tremco, Inc.; Tremco Fire Protection Systems Group.
 - f. USG Corporation.
- C. Exposed Fire-Resistive Joint Systems: Provide products with flame-spread and smoke-developed indexes of less than 25 and 450, respectively, as determined per ASTM E 84.
- D. VOC Content: Fire-resistive joint system sealants shall comply with the following limits for VOC content when calculated according to 40 CFR 59, Subpart D (EPA Method 24):
 - 1. Architectural Sealants: 250 g/L.
 - 2. Sealant Primers for Nonporous Substrates: 250 g/L.
 - 3. Sealant Primers for Porous Substrates: 775 g/L.
- E. Accessories: Provide components of fire-resistive joint systems, including primers and forming materials, that are needed to install fill materials and to maintain ratings required. Use only components specified by fire-resistive joint system manufacturer and approved by the qualified testing agency for systems indicated.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and conditions, with Installer present, for compliance with requirements for joint configurations, substrates, and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

14434.03

HANSEN HALL - LEVEL 300/400 RENOVATIONS

CONSTRUCTION PACKAGE

3.2 PREPARATION

- A. Surface Cleaning: Clean joints immediately before installing fire-resistive joint systems to comply with fire-resistive joint system manufacturer's written instructions and the following requirements:
 - 1. Remove from surfaces of joint substrates foreign materials that could interfere with adhesion of fill materials.
 - 2. Clean joint substrates to produce clean, sound surfaces capable of developing optimum bond with fill materials. Remove loose particles remaining from cleaning operation.
 - 3. Remove laitance and form-release agents from concrete.
- B. Priming: Prime substrates where recommended in writing by fire-resistive joint system manufacturer using that manufacturer's recommended products and methods. Confine primers to areas of bond; do not allow spillage and migration onto exposed surfaces.
- C. Masking Tape: Use masking tape to prevent fill materials of fire-resistive joint system from contacting adjoining surfaces that will remain exposed on completion of the Work and that would otherwise be permanently stained or damaged by such contact or by cleaning methods used to remove stains. Remove tape as soon as possible without disturbing fire-resistive joint system's seal with substrates.

3.3 INSTALLATION

- A. General: Install fire-resistive joint systems to comply with manufacturer's written installation instructions and published drawings for products and applications indicated.
- B. Install forming materials and other accessories of types required to support fill materials during their application and in position needed to produce cross-sectional shapes and depths required to achieve fire ratings indicated.
 - After installing fill materials and allowing them to fully cure, remove combustible forming materials and other accessories not indicated as permanent components of fire-resistive joint system.
- C. Install fill materials for fire-resistive joint systems by proven techniques to produce the following results:
 - 1. Fill voids and cavities formed by joints and forming materials as required to achieve fireresistance ratings indicated.
 - 2. Apply fill materials so they contact and adhere to substrates formed by joints.
 - 3. For fill materials that will remain exposed after completing the Work, finish to produce smooth, uniform surfaces that are flush with adjoining finishes.

3.4 IDENTIFICATION

A. Identify fire-resistive joint systems with preprinted metal or plastic labels. Attach labels permanently to surfaces adjacent to and within 6 inches (150 mm) of joint edge so labels will be visible to anyone seeking to remove or penetrate joint system. Use mechanical fasteners or

14434.03

HANSEN HALL - LEVEL 300/400 RENOVATIONS

CONSTRUCTION PACKAGE

self-adhering-type labels with adhesives capable of permanently bonding labels to surfaces on which labels are placed. Include the following information on labels:

- 1. The words "Warning Fire-Resistive Joint System Do Not Disturb. Notify Building Management of Any Damage."
- 2. Contractor's name, address, and phone number.
- 3. Designation of applicable testing agency.
- 4. Date of installation.
- 5. Manufacturer's name.
- Installer's name.

3.5 FIELD QUALITY CONTROL

- A. Inspecting Agency: Engage a qualified testing agency to perform tests and inspections.
- B. Where deficiencies are found or fire-resistive joint systems are damaged or removed due to testing, repair or replace fire-resistive joint systems so they comply with requirements.
- C. Proceed with enclosing fire-resistive joint systems with other construction only after inspection reports are issued and installations comply with requirements.

3.6 CLEANING AND PROTECTING

- A. Clean off excess fill materials adjacent to joints as the Work progresses by methods and with cleaning materials that are approved in writing by fire-resistive joint system manufacturers and that do not damage materials in which joints occur.
- B. Provide final protection and maintain conditions during and after installation that ensure fireresistive joint systems are without damage or deterioration at time of Substantial Completion. If damage or deterioration occurs despite such protection, cut out and remove damaged or deteriorated fire-resistive joint systems immediately and install new materials to produce fireresistive joint systems complying with specified requirements.
- 3.7 FIRE-RESISTIVE SYSTEMS SCHEDULE PROVIDE UL_LISTED FIRE-RESISTIVE SYSTEMS SCHEDULE FOR THE FOLLOWING JOINT SYSTEMS:
 - A. Where UL-classified systems are indicated, they refer to system numbers in UL's "Fire Resistance Directory" under product Category XHBN or Category XHDG.
 - B. Where Intertek ETL SEMKO-listed systems are indicated, they refer to design numbers in Intertek ETL SEMKO's "Directory of Listed Building Products" under product category Expansion/Seismic Joints or Firestop Systems.
 - C. Floor-to-Floor, Fire-Resistive Joint Systems.
 - D. Wall-to-Wall, Fire-Resistive Joint Systems.
 - E. Floor-to-Wall, Fire-Resistive Joint Systems.

14434.03

HANSEN HALL - LEVEL 300/400 RENOVATIONS

CONSTRUCTION PACKAGE

- F. Head-of-Wall, Fire-Resistive Joint Systems.
- G. Bottom-of-Wall, Fire-Resistive Joint Systems.
- H. Wall-to-Wall, Fire-Resistive Joint Systems Intended for Use as Corner Guards.
- I. Perimeter Fire-Resistive Joint Systems

END OF SECTION 078446