

MECHANICAL EQUIPMENT SCHEDULE

LINE ITEM	DESCRIPTION	LOAD			UNIT DISCONNECT					WIRE AND CONDUIT SIZE	REMARKS
		VOLTS/PHASE	HORSPower (APPROXIMATE)	TOTAL KILOWATTS	UNIT F.L.A. (MCA)	SAFETY SWITCH BY E.C. OR M.C.	TOGGLE SWITCH BY E.C.	SIZE	MOTOR STARTER NEMA SIZE		
38	EF-9 (NEW EXHAUST FAN)	208/3	2	-	--	EC	-	30A-3P	--	(3)#12,(1)#12G,3/4"C.	NOTES 8, 12
39											

NOTES:

EC = ELECTRICAL CONTRACTOR
MC = MECHANICAL CONTRACTOR
F = FUSED
NF = NON FUSED
CB = CIRCUIT BREAKER IN PANEL

1. EC TO FURNISH, INSTALL AND CONNECT DISCONNECT SWITCH.
2. DISCONNECT SWITCH AND POWER TO REMAIN INTACT.
3. EC TO FURNISH, INSTALL AND CONNECT COMBINATION STARTER/DISCONNECT SWITCH.
4. NEMA 3R ENCLOSURE FOR DISCONNECT SWITCH.
5. UNIT PROVIDED WITH FACTORY MOUNTED, NON-POWERED RECEPTACLE.
6. EF-1 THRU 4 SHALL BE INTERLOCKED WITH RTU-12 AND 13. COORDINATE WITH MECHANICAL CONTRACTOR.
7. FAN CONTROLLED BY SWITCH WITH PILOT LIGHT.

8. FAN TO BE INTERLOCKED WITH DAMPER. COORDINATE WITH MECHANICAL CONTRACTOR.
9. EC TO PROVIDE ELECTRIC WALL HEATER EQUAL OR SIMILAR TO 'OMARK' #CWH3507F WITH SURFACE MOUNTING FRAME #CWH3SM WITH INTERNAL DISCONNECT SWITCH.
10. FAN PROVIDED WITH VARIABLE FREQUENCY DRIVE TO CONTROL EXHAUST FAN. COORDINATE REQUIREMENTS WITH MC.
11. FAN CONTROLLED BY VARIABLE SPEED SWITCH. SWITCH PROVIDED BY MC, INSTALLED AND WIRED BY EC.
12. FAN CONTROLLED BY THERMOSTAT.

DESCRIPTION: ADDENDUM #4 - COMPRESSOR EXHAUST

PROPOSAL REQUEST: -

DRAWING NUMBER: E6.4

PROJECT: ECC

SUPPLEMENTAL DRAWING - 6



830A E. Independence Dr.
 Union, Missouri 63084
 638-084-0540 (tel.)
 638-084-0812 (fax)
 mail@cochranseng.com

- Civil Engineering
- Land Surveying
- Architecture
- Site Development
- General Consulting
- Master Planning

DATE BY: RAB

DATE: 02/17/16

PROJECT: 15-6038